

BRUHAT BANGALORE MAHANAGAR PALIKE

Project Division, Yelahanka Zone

SCHEDULE - B

BBMP/2018-19/OW/WORK INDENT34583

Improvements to roads and footpath maintenance in ward no.03

SNo	Quantity	Item Name	Unit	Rates quoted by Sri. CHARAN N S	
				In figures	In words
1	58.50	Dismantling of existing structures like culverts, bridges, retaining walls and other structure comprising of masonry, cement concrete, wood work, steel work, including T&P and scaffolding wherever necessary, sorting the dismantled material, disposal of unserviceable material and stacking the serviceable material with all lifts complete as per specifications. KSRRB M200-13.1. -do- II. By Mechanical Means. A. Cement Concrete	Cum	600.00	Rupees Six Hundred Only
2	78.00	Construction of embankment with approved material Gravel/Murum with all lifts and leads, transporting to site, spreading, grading to required slope and compacting to meet requirement Table 300-2 complete as per specifications, including cost of gravel / murum, watering charges & compaction by vibratory roller to 95% of modified proctors density.	Cum	450.00	Rupees Four Hundred Fifty Only
3	390.00	Providing and laying heavy duty cobble stones interlock pavers, using cement and course sand for manufacture of blocks of approved size, shape and colour with a minimum compressive strength of 281 kg per sqm over 50mm thick sand bed (average thickness) and compacting with plate vibrator having 3 tons compaction force thereby forcing part of sand underneath to come up in between joints, final compaction of paver surface joints into its final level, including cost of materials, labour and HOM complete as per specifications.	Sqm	1200.00	Rupees One Thousand Two Hundred Only
4	3.90	Providing and laying in position plain cement concrete of Mix 1:2:4 with OPC @ 240kgs, with 20mm and down size graded granite metal coarse aggregates @ 0.878 cum and fine aggregates @ 0.53cum, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation, plinth and cills, including cost of all materials, labour, HOM curing complete as per specifications.	Cum	6000.00	Rupees Six Thousand Only
5	433.00	Providing and fixing pre cast solid cement concrete kerb stones made out of CC 1:2:4 with top and bottom width 114 and 165 mm respectively, 400mm high and 450mm in length finished with CM 1:3 plastering and finishing cutting including formwork, curing, including cost of materials, labour charges of machinery, loading and unloading, lead and lift, transportation etc., complete. As per the direction of Engineer incharge.	Nos	500.00	Rupees Five Hundred Only
6	68.25	Painting two coats after filling the surface with synthetic enamel paint in approved shades on new plastered concrete surfaces, with materials, labour complete as per specifications.	Sqm	101.10	Rupees One Hundred One And Paise Ten Only
7		GST @ 12%			

Contractor

Executive Engineer
Project Division
Yelahanka Zone

8/3/19